


Landscape and Biodiversity Measures



- 1. Hedgerow restoration to detailed hedgerow conservation plan.
- 2. Late mow strip between managed margin and hedgerow in filled with swathes of bluebells, Hyacinthoides non scripta, snowdrops, Galanthus nivalis and maintained to allow for a diversity of plant species. This strip to be mowed during routine hedgerow maintenance after 1 September. The aim is to generate a visually pleasing and biodiverse area along the managed margin which will make the heritage trail interesting in all seasons.
- 3. Retain tree cover and under-story. Routine maintenance for road safety.
- 4. New planting to replace tree loss and future tree loss and to compensate for the likely demise of most local ash stands. Trees to be slightly out from existing neat hedge to allow small section of hand maintenance and to allow machine operated hedge cutters to continue without stop every 10 m.
- 5. No new tree planting on this side of the lane.
- 6. Infill tree planting to compensate for the future loss of ash stand on southernmost side of the lane. Species diversity to offset effect of potential future disease

Project : Old Kilcullen Heritage Trail
Drawing : Landscape Plan
Drawing No. OKLB02r
Drawn By : GH
Date : 1/07/'24
Scale : 1:1500@A1



www.hayesryan.com
Kilmead, Athy, Co. Kildare.
info@hayesryan.com
086 2219021
Tel 059 8626093