Specimen Trees

Species	Qty	Form	Age / Condition	Girth	Height	Roots	Notes
Betula Pendula	_	2m Clear stem	3 x transplanted	20 - 25cm	4.5-5m	Rootball	Well balanced crown
Pyrus calleryana 'Chanticleer'	_	2m Clear stem	3 x transplanted	20 - 25cm	4.5-5m	Rootball	Well balanced crown
Sorbus aria	_	2m Clear stem	3 x transplanted	20 - 25cm	4.5-5m	Rootball	Well balanced crown
Liquidambar Styraciflua Worplesdon	_	2m Clear stem	3 x transplanted	20 - 25cm	4.5-5m	Rootball	Well balanced crown

Shrub Mix 1

Species	Designation	Root Type	Height mm	Spread mm	Total plants / sq.m	% Mix in Area
Nepeta "Six Hills Giant"	Container Grown	2 Litre Pot	200-400	200-300	4	10%
Achillea millefolium 'Summer pastels'	Container Grown	2 Litre Pot	200-400	200-300	5	10%
Sarcococca hookeriana	Container Grown	2 Litre Pot	200-400	200-300	4	20%
Pittosporum tobira	Container Grown	3 Litre Pot	200-400	200-300	2	10%
Helleborus x hybridus	Container Grown	3 Litre Pot	400-600	200-300	4	10%
Molina caerulea	Container Grown	3 Litre Pot	100-200	300	4	20%
Vinca minor 'alba'	Container Grown	2 Litre Pot	200-400	200-300	10	10%
Carex oshimensis 'Everest'	Container Grown	2 Litre Pot	200-400	200-300	4	10%

Shrub Mix 2

Species	Designation	Root Type	Height mm	Spread mm	Total plants / sq.m	% Mix in Area
Echinops ritro 'Veitch's Blue'	Container Grown	3 Litre Pot	200-400	300-500	5	20%
Brunnera	Container Grown	2 Litre Pot	200-400	300-400	5	20%
Geum 'Prinses juliana'	Container Grown	5 Litre Pot	200-400	300-500	3	15%
Helleborus 'Spring Velvet'	Container Grown	5 Litre Pot	200-400	400-500	4	15%
Stipa tenuissima	Container Grown	3 Litre Pot	200-400	200-300	3	15%
Achillea filipendulina 'Coronation gold'	Container Grown	3 Litre Pot	100-200	300	4	15%

AECOM

PROJECT

KILDARE MARKET SQUARE

CLIENT

KILDARE CO. COUNCIL
Devoy Park, Naas Co. Kildare
W91 X77F
045980200 tel
https://kildare.ie/countycouncil/index.html

CONSULTANT

AECOM
24 Hatch Street Lower, Saint Kevin's
Dublin, Ireland, D02 TY88
+353 (0) 1 676 3671
https://aecom.com/

LEGEND

HARDSCAPE
- PAVING TYPE 1 - SMALL
- PAVING TYPE 2 - MEDIUM
- PAVING TYPE 3 - LARGE
- PAVING TYPE 4 - BANDING
- PAVING TYPE 5 - TACTILE
- CHANGE IN PAVING ORIENTATION

SOFTSCAPE
- PROPOSED TREE
- EXISTING TREE RETAINED
- SHRUB MIX 1 SEE SOFTWORKS SCHEDULE
- SHRUB MIX 2 SEE SOFTWORKS SCHEDULE

ISSUE/REVISION

I/R	DATE	DESCRIPTION
03	15/01/24	ISSUED FOR PART 8
02	15/12/23	ISSUED FOR PART 8
01	15/08/23	DRAFT PART 8 DOCUMENTATION

KEY PLAN

FOR INFORMATION ONLY

SCALE

1:250 @A1
0 6.25 12.5 m
N

PROJECT NUMBER

60685761

SHEET TITLE

GENERAL ARRANGEMENT LANDSCAPE LAYOUT

SHEET NUMBER

60594179-SHT-30-0000-L-1001

This drawing has been prepared for the use of AECOM's client. It may not be used, modified, reproduced or relied upon by third parties, except as agreed by AECOM or as required by law. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that uses or relies on this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

ISO A1 594mm x 841mm
Approved: ROC
Checked: DB
Designer: AS
Project Management Initials:

Filename:
\\NA.AECOMNET.COM\LFS\EMEA\DUBLIN-IEDBL1\LEGACY\IEDBL1FP001\UFI\JOBS\PR-384133_KILDARE-NEWBRIDGE-TOWN\900_CAD_GIS\906_LA\02_SHEETS\KMS_ACM-XX-00-DR-LA-20-1000.DWG
Last saved by: BHATD1 Last Plotted: 2024-01-15

Printed on ___% Post-Consumer Recycled Content Paper